



PIPE CROSSING UNDER ROADWAY

NOTE :

EXCAVATION BETWEEN DITCH LINES OR WITHIN 5'-0" OF THE SHOULDER IF THERE IS NO DITCH IS PROHIBITED. VERIFY THE LENGTH OF ENCASEMENT AT EACH ROADWAY CROSSING AND NOTIFY THE ENGINEER PRIOR TO INSTALLATION IF THE LENGTH NOTED ON THE PLANS IS INSUFFICIENT.

INSTALL FIELD LOK GASKETS WITHIN ALL ENCASEMENT PIPE AND ONE PIPE LENGTH OUTSIDE OF THE CASING ON BOTH ENDS.

CASING INSULATORS SHALL BE MODEL S8G-2 AS MFR. BY PSI, 6525 GOFORTH ST., HOUSTON, TX. 77021 OR EQUIVALENT. SPACE AT 6'-0"max. C/C.

CASING SEALS SHALL BE MODEL S AS MFR. BY PSI OR EQUIVALENT.

THE UNIT PRICE FOR STEEL ENCASEMENT SHALL INCLUDE ALL ACCESSORY ITEMS SUCH AS FIELD LOK GASKETS, CASING SPACERS, & CASING SEALS.

CASING SPACERS AND END SEALS ARE NOT REQUIRED FOR HDPE ENCASEMENT.